

## Tire Pressure Monitoring System Front Antenna (86.53.16)

### Removal

1.



**WARNING:** Do not work on or under a vehicle supported only by a jack. Always support the vehicle on safety stands.

Raise and support the vehicle.

2.


Remove the fender splash shield. For additional information, refer to [Fender Splash Shield \(76.10.48\)](#) (Section 501-02)

3.

Remove the tire pressure antenna.



Remove the 2 retainers.



### Installation

1.

To install, reverse the removal procedure.

2.

Initiate a new tire pressure antenna using T4.